

<b>Summary of EN 12976 Test Results,</b> annex to Solar KEYMARK Certificate Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b>	<b>011 - 7S1281 A</b>
	Registernummer	
	Num. d'enregistrement	
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b>	Velux A/S	<b>Country/Land/Pays</b>	Denmark
<b>Street / Straße / Rue</b>	Aadalsvej 99	<b>Website</b>	<a href="http://www.velux.com">www.velux.com</a>
<b>Postal Code, Place / PLZ, Ort / Code postal, Place</b>	DK-2970 Hoersholm	<b>E-mail</b>	<a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a>
		<b>Tel. / Fax</b>	+45 45 16 40 29


<b>System classification / G / F</b>	
<b>Flow principle / G / F</b>	Forced / G / F
<b>Direct / indirect / G / F</b>	Indirect / G / F
<b>Press. principle / G / F</b>	Closed / G / F
<b>Drain back/down / G / F</b>	No drain (always filled) / G / F
<b>Storage location / G / F</b>	Indoor / G / F
<b>Storage position / G / F</b>	Vertical / G / F
<b>Int. back-up / G / F</b>	Indirect G / F
<b>If other: / G / F</b>	English / Deutsch / Francais
<b>EN12976 type / G / F</b>	Solar + suppl. / G / F

<b>Collector(s) / Kollektor(en) / Capteur(s)</b>					<b>Storage(s) / Akkumulator(en) / F</b>						
<b>Company / Hersteller / Manufactuer</b> Velux A/S					<b>Company / Hersteller / Manufactuer</b> Velux A/S						
Keymark reg. no. (optional) 011 - 7S 1279 F											
<b>Model</b> Bezeichnung Modèle	<b>Per module / G / F</b>				<b>No. modules</b> G F	<b>Model</b> Bezeichnung Modèle	<b>Total volume</b> G F litres	<b>Gross diameter/width</b> Diam. / Breite (Außenmaß) Diam. / Largeur hors Tout	<b>Höhe (Außenmaß)</b> Höhe (Außenmaß) épaisseur hors tout	<b>Back-up heated volume</b> G F litres	<b>El. back-up power</b> G F kW
	<b>Aperture area (Aa)</b> Aperturfläche (Aa) Superficie d'entrée (Aa)	<b>Gross length</b> Länge (Außenmaß) Longueur Hors tout	<b>Gross width</b> Breite (Außenmaß) Largeur hors Tout	<b>min - max</b>							
	m <sup>2</sup>	m	m				mm	mm			
CLI U12 5000	2.158	1.829	1.374	1 - 3	TFF 200 0201	180	540	1432	-	-	
CLI S08 5000	1.385	1.427	1.174	2 - 5	TFF 300 0201	280	600	1794	-	-	
CLI S06 5000	1.152	1.207	1.174	2 - 6	TFF 400 0201	375	700	1591	-	-	
CLI M08 5000	0.915	1.427	0.814	2 - 8							

<b>Controller / G / F</b>			<b>Fluid / G / F</b>		
<b>Company/Hersteller/Manufacteur</b> Velux A/S			<b>Company/Hersteller/Manufacteur</b> TYFOROP CHEMIE GmbH		
<b>Model / Bezeichnung / Modèle</b> SKSC2			<b>Model / Bezeichnung / Modèle</b> Tyfocor L		
<b>Functions</b>	English Deutsch Francais		<b>Freezing point</b>	-50 °C	
G			G		
F			F		

<b>System family overview / G / F</b>											
<b>Collector</b> G F	<b>No. collectors / G / F</b>										
	<b>Storage / G / F</b>										
	TFF 200 0201			TFF 300 0201			TFF 400 0201			0	
CLI U12 5000	1			2			3				
CLI S08 5000	2			3			4	5			
CLI S06 5000	2			3	4		5	6			
CLI M08 5000	2	3		4	5		6	7	8		

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüfberichtsnummer / F</b>	SYS10_03
<b>Date of test report / Datum G / date F</b>	06.09.2011

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b>	 <p>Testzentrum Saarbrücken Altenkesseler Str. 17 Gebäude D2 66115 Saarbrücken</p>
Die Systeme wurden mit den zusätzlich erforderlichen und eingebauten Sicherheitskomponenten für Großbritannien geprüft / The systems were tested with the additional and necessary safety components for Great Britain	

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												2 x CLI U12 + TFF 30
<b>Collector type</b> G F	CLI U12 5000	<b>No. collectors</b> G F	2	<b>Storage type</b> G F	TFF 300 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	170	200	250	170	200	250	170	200	250	170	200	250
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	9 492	11 164	13 970	9 240	10 848	13 403	4 762	5 834	7 789	342	342	342
Würzburg, DE	9 114	10 691	13 371	9 051	10 565	12 930	4 478	5 424	7 064	342	342	342
Davos, CH	10 281	12 110	15 137	10 281	12 078	15 043	2 775	3 784	5 834	342	342	342
Athens, GR	7 064	8 326	10 407	7 064	8 326	10 375	1 261	1 734	2 712	342	342	342

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>
	Q <sub>L</sub>	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F		Stockholm	Würzburg DE	Davos CH	Athens GR		
	G	4 163	4 415	6 055	6 181		
	T <sub>a</sub>	7.5	9.0	3.2	18.5		
	T <sub>c</sub>	8.5	10.0	5.4	17.8		
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2		

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Français	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement Date / Datum / Date	<b>011 - 7S1281 A</b>  30.06.2011
--	---	---

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> Website E-mail Tel. / Fax	Denmark www.velux.com steffen.bay@velux.com +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

Name of system konfiguration / G / F												2 x CLI M08 + TFF 20
Collector type G F	CLI M08 5000	No. collectors G F	2	Storage type G F	TFF 200 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	80	110	140	80	110	140	80	110	140	80	110	140
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	4 478	6 150	7 821	4 447	6 055	7 537	3 305	4 491	5 708	342	342	342
Würzburg, DE	4 289	5 897	7 506	4 289	5 834	7 316	3 053	4 160	5 326	342	342	342
Davos, CH	4 857	6 654	8 483	4 857	6 055	7 537	2 466	4 491	5 708	342	342	342
Athens, GR	3 343	4 573	5 834	3 343	4 573	5 803	1 381	1 974	2 715	342	342	342

Perf. indicators G F	Q <sub>d</sub>	Heat demand / G / F
	Q <sub>L</sub>	System output / G / F
	f <sub>sol</sub>	QL/Q <sub>d</sub> ; solar fraction / G / F
	Q <sub>par</sub>	Elec. for pumps/controllers / G / F

Ref. conditions G F		Stockholm	Würzburg DE	Davos CH	Athens GR
	G	4 163	4 415	6 055	6 181
	T <sub>a</sub>	7.5	9.0	3.2	18.5
	T <sub>c</sub>	8.5	10.0	5.4	17.8
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2

G	kWh/m <sup>2</sup>	Annual irradiation South, 45° / G / F
T <sub>a</sub>	°C	Annual mean air temp. / G / F
T <sub>c</sub>	°C	Annual mean cold water temp. / G / F
ΔT <sub>c</sub>	°C	Seasonal variation of T <sub>c</sub> / G / F
T <sub>h</sub>	45°C	Desired (mix. valve) temp. / G / F

Max. operating press. - collector side G F	600	kPa	Max. operating press. - tank side G F	1 000	kPa
--	-----	-----	---	-------	-----

Testing Laboratory / Prüflaboratorium / Laboratoire d'essais	IZES gGmbH, TZSB
Website	www.izes.de/tzsb/
Test report id. number / Prüberichtnummer / F	SYS10_03
Date of test report / G / F	06.09.2011
Test method / G / F	ISO 9459-5 (DST)

Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire English Deutsch Francais	Stamp & signature of test lab
---	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												1 x CLI U12 + TFF 20
<b>Collector type</b> G F	CLI U12 5000	<b>No. collectors</b> G F	1	<b>Storage type</b> G F	TFF 200 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	80	110	140	80	110	140	80	110	140	80	110	140
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	4 478	6 150	7 821	4 447	6 086	7 537	3 040	4 188	5 323	342	342	342
Würzburg, DE	4 289	5 897	7 506	4 289	5 834	7 316	2 791	4 160	4 926	342	342	342
Davos, CH	4 857	6 654	8 483	4 857	6 654	8 420	2 053	3 154	4 447	342	342	342
Athens, GR	3 343	4 573	5 834	3 343	4 573	5 834	1 120	1 621	2 302	342	342	342

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>
	Q <sub>L</sub>	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F	Stockholm	Würzburg DE	Davos CH	Athens GR	
	G	4 163	4 415	6 055	6 181
	T <sub>a</sub>	7.5	9.0	3.2	18.5
	T <sub>c</sub>	8.5	10.0	5.4	17.8
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Francais	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

**Name of system konfiguration / G / F** 2 x CLI S06 + TFF 20

<b>Collector type</b> G F	CLI S06 5000	<b>No. collectors</b> G F	2	<b>Storage type</b> G F	TFF 200 0201
---------------------------------	--------------	---------------------------------	---	-------------------------------	--------------

**Calculated annual results / G / F**

Location G F	Daily draw-off litres/day / G / F /											
	80	110	140	80	110	140	80	110	140	80	110	140
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	4 478	6 150	7 821	4 447	6 086	7 537	2 936	4 056	5 166	342	342	342
Würzburg, DE	4 289	5 897	7 506	4 289	5 834	7 316	2 696	3 696	4 768	342	342	342
Davos, CH	4 857	6 654	8 483	4 857	6 654	8 452	1 895	2 933	4 226	342	342	342
Athens, GR	3 343	4 573	5 834	3 343	4 573	5 834	1 025	1 498	2 144	342	342	342

<b>Perf. indicators</b> G F	Q <sub>d</sub>	Heat demand / G / F
	Q <sub>L</sub>	System output / G / F
	f <sub>sol</sub>	QL/Q <sub>d</sub> ; solar fraction / G / F
	Q <sub>par</sub>	Elec. for pumps/controllers / G / F

<b>Ref. conditions</b> G F		Stockholm	Würzburg DE	Davos CH	Athens GR		
	G	4 163	4 415	6 055	6 181		
	T <sub>a</sub>	7.5	9.0	3.2	18.5		
	T <sub>c</sub>	8.5	10.0	5.4	17.8		
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2		

G	kWh/m <sup>2</sup>	Annual irradiation South, 45° / G / F
T <sub>a</sub>	°C	Annual mean air temp. / G / F
T <sub>c</sub>	°C	Annual mean cold water temp. / G / F
ΔT <sub>c</sub>	°C	Seasonal variation of T <sub>c</sub> / G / F
T <sub>h</sub>	45°C	Desired (mix. valve) temp. / G / F

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b> <b>Website</b> <b>Test report id. number / Prüberichtnummer / F</b> <b>Date of test report / G / F</b> <b>Test method / G / F</b>	IZES gGmbH, TZSB <a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a> SYS10_03 06.09.2011 ISO 9459-5 (DST)
---	--

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Francais	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>											<b>3 x CLI M08 + TFF 20</b>	
<b>Collector type</b> G F	CLI M08 5000			<b>No. collectors</b> G F	3			<b>Storage type</b> G F	TFF 200 0201			

Calculated annual results / G / F																		
Location G F	Daily draw-off litres/day / G / F /																	
	110			140			170			110			140			170		
	l/d			l/d			l/d			l/d			l/d			l/d		
Q <sub>d</sub> MJ/y			QL MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y									
Stockholm, SE	6 150	7 821	9 492	6 068	6 433	9 114	3 712	3 642	6 042	342	342	342						
Würzburg, DE	5 897	7 506	9 114	5 834	7 348	8 735	3 378	4 393	5 456	342	342	342						
Davos, CH	6 654	8 483	10 281	6 654	8 452	10 186	2 428	3 564	4 920	342	342	342						
Athens, GR	4 573	5 834	7 064	4 573	5 834	7 064	1 198	1 734	2 428	342	342	342						

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>
	Q <sub>L</sub>	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F		Stockholm	Würzburg DE	Davos CH	Athens GR		
	G	4 163	4 415	6 055	6 181		
	T <sub>a</sub>	7.5	9.0	3.2	18.5		
	T <sub>c</sub>	8.5	10.0	5.4	17.8		
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2		

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Francais	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement Date / Datum / Date	<b>011 - 7S1281 A</b>  30.06.2011
--	---	---

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> Website E-mail Tel. / Fax	Denmark www.velux.com steffen.bay@velux.com +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

Name of system konfiguration / G / F											2 x CLI S08 + TFF 20	
Collector type G F	CLI S08 5000	No. collectors G F	2	Storage type G F	TFF 200 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	110	140	170	110	140	170	110	140	170	110	140	170
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y			
Stockholm, SE	6 150	7 821	9 492	6 086	7 569	9 114	3 696	4 756	6 020	342	342	342
Würzburg, DE	5 897	7 506	9 114	5 866	7 348	8 735	3 396	4 374	5 424	342	342	342
Davos, CH	6 654	8 483	10 281	6 654	8 452	10 186	4 257	4 920	5 298	342	342	342
Athens, GR	4 573	5 834	7 064	4 573	5 834	7 064	1 167	1 734	2 397	342	342	342

Perf. indicators G F	Q <sub>d</sub>	Heat demand / G / F										
	Q <sub>L</sub>	System output / G / F										
	f <sub>sol</sub>	QL/Q <sub>d</sub> ; solar fraction / G / F										
	Q <sub>par</sub>	Elec. for pumps/controllers / G / F										

Ref. conditions G F		Stockholm	Würzburg DE	Davos CH	Athens GR		
	G	4 163	4 415	6 055	6 181		
	T <sub>a</sub>	7.5	9.0	3.2	18.5		
	T <sub>c</sub>	8.5	10.0	5.4	17.8		
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2		

G	kWh/m <sup>2</sup>	Annual irradiation South, 45° / G / F				
T <sub>a</sub>	°C	Annual mean air temp. / G / F				
T <sub>c</sub>	°C	Annual mean cold water temp. / G / F				
ΔT <sub>c</sub>	°C	Seasonal variation of T <sub>c</sub> / G / F				
T <sub>h</sub>	45°C	Desired (mix. valve) temp. / G / F				

Max. operating press. - collector side G F	600	kPa	Max. operating press. - tank side G F	1 000	kPa
--	-----	-----	---	-------	-----

Testing Laboratory / Prüflaboratorium / Laboratoire d'essais	IZES gGmbH, TZSB
Website	www.izes.de/tzsb/
Test report id. number / Prüberichtnummer / F	SYS10_03
Date of test report / G / F	06.09.2011
Test method / G / F	ISO 9459-5 (DST)

Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire English Deutsch Français	Stamp & signature of test lab
---	-------------------------------

<b>Summary of EN 12976 Test Results,</b> <b>annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												<b>3 x CLI S06 + TFF 300</b>			
<b>Collector type</b> G F	CLI S06 5000			<b>No. collectors</b> G F			3			<b>Storage type</b> G F			TFF 300 0201		

Calculated annual results / G / F																		
Location G F	Daily draw-off litres/day / G / F /																	
	140			170			200			140			170			200		
	l/d			l/d			l/d			l/d			l/d			l/d		
Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y									
Stockholm, SE	7 821	9 492	11 164	7 695	9 240	10 817	4 595	5 613	6 780	342	342	342						
Würzburg, DE	7 506	9 114	10 691	7 411	9 051	10 533	4 163	5 298	6 307	342	342	342						
Davos, CH	8 483	10 281	12 110	8 452	10 281	12 078	2 838	3 942	5 172	342	342	342						
Athens, GR	5 834	7 064	8 326	5 834	7 064	8 326	1 451	1 955	2 523	342	342	342						

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>											
	Q <sub>L</sub>	<b>System output / G / F</b>											
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>											
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>											

<b>Ref. conditions</b> G F		Stockholm	Würzburg DE	Davos CH	Athens GR							
	G	4 163	4 415	6 055	6 181							
	T <sub>a</sub>	7.5	9.0	3.2	18.5							
	T <sub>c</sub>	8.5	10.0	5.4	17.8							
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2							

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>										
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>										
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>										
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>										
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>										

<b>Max. operating press. - collector side</b> G F	600 kPa		<b>Max. operating press. - tank side</b> G F	1 000 kPa	
---	---------	--	--	-----------	--

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Français	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												4 x CLI M08 + TFF 30
<b>Collector type</b> G F	CLI M08 5000	<b>No. collectors</b> G F	4	<b>Storage type</b> G F	TFF 300 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	140	170	200	140	170	200	140	170	200	140	170	200
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	7 821	9 492	11 164	7 695	9 240	10 817	4 447	5 424	6 591	342	342	342
Würzburg, DE	7 506	9 114	10 691	7 411	9 051	10 533	4 037	5 140	6 118	342	342	342
Davos, CH	8 483	10 281	12 110	8 452	10 281	12 078	2 617	3 690	4 857	342	342	342
Athens, GR	5 834	7 064	8 326	5 834	7 064	8 326	1 325	1 798	2 334	342	342	342

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>
	Q <sub>L</sub>	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F	Stockholm Würzburg DE Davos CH Athens GR				
	G	4 163	4 415	6 055	6 181
	T <sub>a</sub>	7.5	9.0	3.2	18.5
	T <sub>c</sub>	8.5	10.0	5.4	17.8
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Français	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												<b>3 x CLI S08 + TFF 300</b>
<b>Collector type</b> G F	CLI S08 5000	<b>No. collectors</b> G F	3	<b>Storage type</b> G F	TFF 300 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	170	200	250	170	200	250	170	200	250	170	200	250
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	9 492	11 164	13 939	9 240	10 848	13 434	5 077	6 181	8 199	342	342	342
Würzburg, DE	9 114	10 691	13 371	9 051	10 565	12 930	4 825	5 771	7 442	342	342	342
Davos, CH	10 281	12 110	15 137	10 281	12 078	15 043	3 154	4 194	6 339	342	342	342
Athens, GR	7 064	8 326	10 407	7 064	8 326	10 375	1 482	1 987	2 964	342	342	342

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>
	Q <sub>L</sub>	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F	Stockholm	Würzburg DE	Davos CH	Athens GR		
	G	4 163	4 415	6 055	6 181	
	T <sub>a</sub>	7.5	9.0	3.2	18.5	
	T <sub>c</sub>	8.5	10.0	5.4	17.8	
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2	

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Français	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement Date / Datum / Date	<b>011 - 7S1281 A</b>  30.06.2011
--	---	---

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> Website E-mail Tel. / Fax	Denmark www.velux.com steffen.bay@velux.com +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

Name of system konfiguration / G / F											5 x CLI M08 + TFF 30	
Collector type G F	CLI M08 5000	No. collectors G F	5	Storage type G F	TFF 300 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	200	250	300	200	250	300	200	250	300	200	250	300
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	11 164	13 939	16 746	10 880	13 466	15 831	5 929	7 852	9 839	342	342	342
Würzburg, DE	10 691	13 371	16 052	10 565	12 961	15 137	5 487	7 096	8 767	342	342	342
Davos, CH	12 110	15 137	18 165	12 110	15 043	17 786	3 784	5 740	7 916	342	342	342
Athens, GR	8 326	10 407	12 488	8 326	10 375	12 394	1 734	2 649	3 753	342	342	342

Perf. indicators G F	Q <sub>d</sub>	Heat demand / G / F
	Q <sub>L</sub>	System output / G / F
	f <sub>sol</sub>	QL/Q <sub>d</sub> ; solar fraction / G / F
	Q <sub>par</sub>	Elec. for pumps/controllers / G / F

Ref. conditions G F		Stockholm	Würzburg DE	Davos CH	Athens GR		
	G	4 163	4 415	6 055	6 181		
	T <sub>a</sub>	7.5	9.0	3.2	18.5		
	T <sub>c</sub>	8.5	10.0	5.4	17.8		
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2		

G	kWh/m <sup>2</sup>	Annual irradiation South, 45° / G / F
T <sub>a</sub>	°C	Annual mean air temp. / G / F
T <sub>c</sub>	°C	Annual mean cold water temp. / G / F
ΔT <sub>c</sub>	°C	Seasonal variation of T <sub>c</sub> / G / F
T <sub>h</sub>	45°C	Desired (mix. valve) temp. / G / F

Max. operating press. - collector side G F	600	kPa	Max. operating press. - tank side G F	1 000	kPa
--	-----	-----	---	-------	-----

Testing Laboratory / Prüflaboratorium / Laboratoire d'essais	IZES gGmbH, TZSB
Website	www.izes.de/tzsb/
Test report id. number / Prüberichtnummer / F	SYS10_03
Date of test report / G / F	06.09.2011
Test method / G / F	ISO 9459-5 (DST)

Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire English Deutsch Francais	Stamp & signature of test lab
---	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												4 x CLI S06 + TFF 30			
<b>Collector type</b> G F	CLI S06 5000			<b>No. collectors</b> G F			4			<b>Storage type</b> G F			TFF 300 0201		

Calculated annual results / G / F																		
Location G F	Daily draw-off litres/day / G / F /																	
	200			250			300			200			250			300		
	l/d			l/d			l/d			l/d			l/d			l/d		
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y								
Stockholm, SE	11 164	13 939	16 746	10 880	13 466	15 831	5 897	7 821	9 808	342	342	342						
Würzburg, DE	10 691	13 371	16 052	10 565	12 961	15 137	5 487	7 064	8 735	342	342	342						
Davos, CH	12 110	15 137	18 165	12 110	15 043	17 786	3 753	5 708	7 852	342	342	342						
Athens, GR	8 326	10 407	12 488	8 326	10 060	12 394	1 734	2 302	3 721	342	342	342						

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>
	Q <sub>L</sub>	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F	Stockholm	Würzburg DE	Davos CH	Athens GR	
	G	4 163	4 415	6 055	6 181
	T <sub>a</sub>	7.5	9.0	3.2	18.5
	T <sub>c</sub>	8.5	10.0	5.4	17.8
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Français	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> Website E-mail Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

Name of system konfiguration / G / F											6 x CLI M08 + TFF 40	
Collector type G F	CLI M08 5000	No. collectors G F	6	Storage type G F	TFF 400 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	200	250	300	200	250	300	200	250	300	200	250	300
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	11 164	13 939	16 746	11 038	13 781	16 399	5 550	7 285	9 177	342	342	342
Würzburg, DE	10 691	13 371	16 052	10 691	13 245	15 705	5 109	6 591	8 231	342	342	342
Davos, CH	12 110	15 137	18 165	12 110	15 137	18 102	2 870	4 415	6 276	342	342	342
Athens, GR	8 326	10 407	12 488	8 326	10 407	12 457	1 325	1 987	2 838	342	342	342

Perf. indicators G F	Q <sub>d</sub>	Heat demand / G / F
	Q <sub>L</sub>	System output / G / F
	f <sub>sol</sub>	QL/Q <sub>d</sub> ; solar fraction / G / F
	Q <sub>par</sub>	Elec. for pumps/controllers / G / F

Ref. conditions G F		Stockholm	Würzburg DE	Davos CH	Athens GR
	G	4 163	4 415	6 055	6 181
	T <sub>a</sub>	7.5	9.0	3.2	18.5
	T <sub>c</sub>	8.5	10.0	5.4	17.8
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2

G	kWh/m <sup>2</sup>	Annual irradiation South, 45° / G / F
T <sub>a</sub>	°C	Annual mean air temp. / G / F
T <sub>c</sub>	°C	Annual mean cold water temp. / G / F
ΔT <sub>c</sub>	°C	Seasonal variation of T <sub>c</sub> / G / F
T <sub>h</sub>	45°C	Desired (mix. valve) temp. / G / F

Max. operating press. - collector side G F	600	kPa	Max. operating press. - tank side G F	1 000	kPa
--	-----	-----	---	-------	-----

Testing Laboratory / Prüflaboratorium / Laboratoire d'essais	IZES gGmbH, TZSB
Website	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
Test report id. number / Prüberichtsnummer / F	SYS10_03
Date of test report / G / F	06.09.2011
Test method / G / F	ISO 9459-5 (DST)

Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire English Deutsch Francais	Stamp & signature of test lab
---	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement Date / Datum / Date	<b>011 - 7S1281 A</b>  30.06.2011
--	---	---

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> Website E-mail Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

Name of system konfiguration / G / F												4 x CLI S08 + TFF 40
Collector type G F	CLI S08 5000	No. collectors G F	4	Storage type G F	TFF 400 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	250	300	400	250	300	400	250	300	400	250	300	400
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux.net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	13 939	16 746	22 327	13 781	16 399	21 350	7 253	9 145	13 245	342	342	342
Würzburg, DE	13 371	16 052	21 413	13 245	15 705	20 152	6 591	8 199	11 574	342	342	342
Davos, CH	15 137	18 165	24 220	15 137	18 102	23 652	4 352	6 213	10 659	342	342	342
Athens, GR	10 407	12 488	16 651	10 407	12 457	16 556	1 955	2 807	5 077	342	342	342

Perf. indicators G F	Q <sub>d</sub>	Heat demand / G / F
	Q <sub>L</sub>	System output / G / F
	f <sub>sol</sub>	QL/Q <sub>d</sub> ; solar fraction / G / F
	Q <sub>par</sub>	Elec. for pumps/controllers / G / F

Ref. conditions G F		Stockholm	Würzburg DE	Davos CH	Athens GR
	G	4 163	4 415	6 055	6 181
	T <sub>a</sub>	7.5	9.0	3.2	18.5
	T <sub>c</sub>	8.5	10.0	5.4	17.8
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2

G	kWh/m <sup>2</sup>	Annual irradiation South, 45° / G / F
T <sub>a</sub>	°C	Annual mean air temp. / G / F
T <sub>c</sub>	°C	Annual mean cold water temp. / G / F
ΔT <sub>c</sub>	°C	Seasonal variation of T <sub>c</sub> / G / F
T <sub>h</sub>	45°C	Desired (mix. valve) temp. / G / F

Max. operating press. - collector side G F	600	kPa	Max. operating press. - tank side G F	1 000	kPa
--	-----	-----	---	-------	-----

Testing Laboratory / Prüflaboratorium / Laboratoire d'essais	IZES gGmbH, TZSB
Website	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
Test report id. number / Prüberichtnummer / F	SYS10_03
Date of test report / G / F	06.09.2011
Test method / G / F	ISO 9459-5 (DST)

Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire English Deutsch Francais	Stamp & signature of test lab
---	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												5 x CLI S06 + TFF 40
<b>Collector type</b> G F	CLI S06 5000	<b>No. collectors</b> G F	5	<b>Storage type</b> G F	TFF 400 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	250	300	400	250	300	400	250	300	400	250	300	400
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Qd MJ/y			QL MJ/y			Qaux.net MJ/y			Qpar MJ/y		
Stockholm, SE	13 939	16 746	22 327	13 781	16 399	21 350	7 127	8 956	12 993	342	342	342
Würzburg, DE	13 371	16 052	21 413	13 245	15 705	20 183	6 465	8 010	11 384	342	342	342
Davos, CH	15 137	18 165	24 220	15 137	18 102	23 684	4 131	5 960	10 312	342	342	342
Athens, GR	10 407	12 488	16 651	10 407	12 457	16 556	1 861	2 649	4 857	342	342	342

<b>Perf. indicators</b> G F	Qd	<b>Heat demand / G / F</b>
	QL	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Qd; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F	Stockholm	Würzburg DE	Davos CH	Athens GR	
	G	4 163	4 415	6 055	6 181
	Ta	7.5	9.0	3.2	18.5
	Tc	8.5	10.0	5.4	17.8
	ΔTc	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
Ta	°C	<b>Annual mean air temp. / G / F</b>
Tc	°C	<b>Annual mean cold water temp. / G / F</b>
ΔTc	°C	<b>Seasonal variation of Tc / G / F</b>
Th	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Francais	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement Date / Datum / Date	<b>011 - 7S1281 A</b>  30.06.2011
--	---	---

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> Website E-mail Tel. / Fax	Denmark www.velux.com steffen.bay@velux.com +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

Name of system konfiguration / G / F											7 x CLI M08 + TFF 40	
Collector type G F	CLI M08 5000	No. collectors G F	7	Storage type G F	TFF 400 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	250	300	400	250	300	400	250	300	400	250	300	400
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux.net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	13 939	16 746	22 327	13 781	16 399	21 381	6 749	8 515	12 394	342	342	342
Würzburg, DE	13 371	16 052	21 413	13 245	15 736	20 215	6 118	7 632	10 785	342	342	342
Davos, CH	15 137	18 165	24 220	15 137	18 133	23 747	3 595	5 267	9 335	342	342	342
Athens, GR	10 407	12 488	16 651	10 407	12 457	16 556	1 577	2 271	4 320	342	342	342

Perf. indicators G F	Q <sub>d</sub>	Heat demand / G / F
	Q <sub>L</sub>	System output / G / F
	f <sub>sol</sub>	QL/Q <sub>d</sub> ; solar fraction / G / F
	Q <sub>par</sub>	Elec. for pumps/controllers / G / F

Ref. conditions G F		Stockholm	Würzburg DE	Davos CH	Athens GR		
	G	4 163	4 415	6 055	6 181		
	T <sub>a</sub>	7.5	9.0	3.2	18.5		
	T <sub>c</sub>	8.5	10.0	5.4	17.8		
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2		

G	kWh/m <sup>2</sup>	Annual irradiation South, 45° / G / F
T <sub>a</sub>	°C	Annual mean air temp. / G / F
T <sub>c</sub>	°C	Annual mean cold water temp. / G / F
ΔT <sub>c</sub>	°C	Seasonal variation of T <sub>c</sub> / G / F
T <sub>h</sub>	45°C	Desired (mix. valve) temp. / G / F

Max. operating press. - collector side G F	600	kPa	Max. operating press. - tank side G F	1 000	kPa
--	-----	-----	---	-------	-----

Testing Laboratory / Prüflaboratorium / Laboratoire d'essais	IZES gGmbH, TZSB
Website	www.izes.de/tzsb/
Test report id. number / Prüberichtnummer / F	SYS10_03
Date of test report / G / F	06.09.2011
Test method / G / F	ISO 9459-5 (DST)

Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire English Deutsch Francais	Stamp & signature of test lab
---	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												<b>3 x CLI U12 + TFF 40</b>			
<b>Collector type</b> G F	CLI U12 5000			<b>No. collectors</b> G F			3			<b>Storage type</b> G F			TFF 400 0201		

Calculated annual results / G / F																		
Location G F	Daily draw-off litres/day / G / F /																	
	250			300			400			250			300			400		
	l/d			l/d			l/d			l/d			l/d			l/d		
Q <sub>d</sub> MJ/y			QL MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y									
Stockholm, SE	13 939	16 746	22 327	13 781	16 430	21 413	6 717	8 483	12 362	342	342	342						
Würzburg, DE	13 371	16 052	21 413	13 245	15 736	20 246	6 086	7 600	10 754	342	342	342						
Davos, CH	15 137	18 165	24 220	15 137	18 133	23 747	3 532	5 203	9 240	342	342	342						
Athens, GR	10 407	12 488	16 651	10 407	12 457	16 556	1 545	2 239	4 257	342	342	342						

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>											
	Q <sub>L</sub>	<b>System output / G / F</b>											
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>											
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>											

<b>Ref. conditions</b> G F		Stockholm	Würzburg DE	Davos CH	Athens GR			
	G	4 163	4 415	6 055	6 181			
	T <sub>a</sub>	7.5	9.0	3.2	18.5			
	T <sub>c</sub>	8.5	10.0	5.4	17.8			
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2			

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>											
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>											
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>											
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>											
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>											

<b>Max. operating press. - collector side</b> G F	600 kPa			<b>Max. operating press. - tank side</b> G F	1 000 kPa		
---	---------	--	--	--	-----------	--	--

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Français	Stamp & signature of test lab
(Blank space for stamp and signature)	

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												<b>6 x CLI S06 + TFF 40</b>			
<b>Collector type</b> G F	CLI S06 5000			<b>No. collectors</b> G F			6			<b>Storage type</b> G F			TFF 400 0201		

Calculated annual results / G / F																		
Location G F	Daily draw-off litres/day / G / F /																	
	250			300			400			250			300			400		
	l/d			l/d			l/d			l/d			l/d			l/d		
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y								
Stockholm, SE	13 939	16 746	22 327	13 781	16 430	21 413	6 496	8 231	11 984	342	342	342						
Würzburg, DE	13 371	16 052	21 413	13 277	15 736	20 246	5 960	7 379	10 407	342	342	342						
Davos, CH	15 137	18 165	24 220	15 137	18 133	23 810	3 248	4 793	8 704	342	342	342						
Athens, GR	10 407	12 488	16 651	10 407	12 457	16 556	1 388	2 050	3 942	342	342	342						

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>
	Q <sub>L</sub>	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F		Stockholm	Würzburg DE	Davos CH	Athens GR		
	G	4 163	4 415	6 055	6 181		
	T <sub>a</sub>	7.5	9.0	3.2	18.5		
	T <sub>c</sub>	8.5	10.0	5.4	17.8		
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2		

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa		<b>Max. operating press. - tank side</b> G F	1 000 kPa	
---	---------	--	--	-----------	--

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Français	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> Website E-mail Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>												5 x CLI S08 + TFF 40
<b>Collector type</b> G F	CLI S08 5000	<b>No. collectors</b> G F	5	<b>Storage type</b> G F	TFF 400 0201							

Calculated annual results / G / F												
Location G F	Daily draw-off litres/day / G / F /											
	250	300	400	250	300	400	250	300	400	250	300	400
	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d	l/d
	Q <sub>d</sub> MJ/y			Q <sub>L</sub> MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y		
Stockholm, SE	13 939	16 746	22 327	13 781	16 430	21 413	6 496	8 199	11 984	342	342	342
Würzburg, DE	13 371	16 052	21 413	13 277	15 736	20 246	5 929	7 348	10 407	342	342	342
Davos, CH	15 137	18 165	24 220	15 137	18 133	23 810	3 248	4 793	8 672	342	342	342
Athens, GR	10 407	12 488	16 651	10 407	12 457	16 556	1 388	2 018	3 942	342	342	342

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>
	Q <sub>L</sub>	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F	Stockholm	Würzburg DE	Davos CH	Athens GR	
	G	4 163	4 415	6 055	6 181
	T <sub>a</sub>	7.5	9.0	3.2	18.5
	T <sub>c</sub>	8.5	10.0	5.4	17.8
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> English Deutsch Français	Stamp & signature of test lab
--	-------------------------------

<b>Summary of EN 12976 Test Results, annex to Solar KEYMARK Certificate</b> Kurzfassung EN 12976 Test Ergebnisse, Anlage zum Solar KEYMARK-Zertifikat Synthèse des résultats d'essais selon EN 12976, Annexe au certificat Solar	<b>Registration No.</b> Registernummer Num. d'enregistrement	<b>011 - 7S1281 A</b>
	<b>Date / Datum / Date</b>	<b>30.06.2011</b>

<b>Company / Firma / Société</b> Street / Straße / Rue Postal Code, Place / PLZ, Ort / Code postal, Place	Velux A/S Aadalsvej 99 DK-2970 Hoersholm	<b>Country/Land/Pays</b> <b>Website</b> <b>E-mail</b> Tel. / Fax	Denmark <a href="http://www.velux.com">www.velux.com</a> <a href="mailto:steffen.bay@velux.com">steffen.bay@velux.com</a> +45 45 16 40 29
---	--	---	--

System family overview / G / F												
Collector type G F	Number of collectors / G / F											
	Storage type / G / F											
	TFF 200 0201			TFF 300 0201			TFF 400 0201					
CLI U12 5000	1			2			3					
CLI S08 5000	2			3			4	5				
CLI S06 5000	2			3	4		5	6				
CLI M08 5000	2	3		4	5		6	7	8			

<b>Name of system konfiguration / G / F</b>											<b>8 x CLI M08 + TFF 40</b>	
<b>Collector type</b> G F	CLI M08 5000			<b>No. collectors</b> G F	8			<b>Storage type</b> G F	TFF 400 0201			

Calculated annual results / G / F																		
Location G F	Daily draw-off litres/day / G / F /																	
	300			400			570			300			400			570		
	l/d			l/d			l/d			l/d			l/d			l/d		
Q <sub>d</sub> MJ/y			QL MJ/y			Q <sub>aux,net</sub> MJ/y			Q <sub>par</sub> MJ/y									
Stockholm, SE	16 746	22 327	33428*	16 430	21 444	29738*	8 010	11 700	18859*	342	342	342*						
Würzburg, DE	16 052	21 413	32167*	15 736	20 278	29013*	7 159	10 155	17471*	342	342	342*						
Davos, CH	18 165	24 220	36266*	18 133	23 841	34059*	4 478	8 199	17029*	342	342	342*						
Athens, GR	12 488	16 651	24945*	12 457	16 588	24693*	1 861	3 690	8704*	342	342	342*						

<b>Perf. indicators</b> G F	Q <sub>d</sub>	<b>Heat demand / G / F</b>
	Q <sub>L</sub>	<b>System output / G / F</b>
	f <sub>sol</sub>	<b>QL/Q<sub>d</sub>; solar fraction / G / F</b>
	Q <sub>par</sub>	<b>Elec. for pumps/controllers / G / F</b>

<b>Ref. conditions</b> G F		Stockholm	Würzburg DE	Davos CH	Athens GR		
	G	4 163	4 415	6 055	6 181		
	T <sub>a</sub>	7.5	9.0	3.2	18.5		
	T <sub>c</sub>	8.5	10.0	5.4	17.8		
	ΔT <sub>c</sub>	2.1 - 14.9	7.0 - 13.0	4.6 - 6.2	10.4 - 25.2		

G	kWh/m <sup>2</sup>	<b>Annual irradiation South, 45° / G / F</b>
T <sub>a</sub>	°C	<b>Annual mean air temp. / G / F</b>
T <sub>c</sub>	°C	<b>Annual mean cold water temp. / G / F</b>
ΔT <sub>c</sub>	°C	<b>Seasonal variation of T<sub>c</sub> / G / F</b>
T <sub>h</sub>	45°C	<b>Desired (mix. valve) temp. / G / F</b>

<b>Max. operating press. - collector side</b> G F	600 kPa	<b>Max. operating press. - tank side</b> G F	1 000 kPa
---	---------	--	-----------

<b>Testing Laboratory / Prüflaboratorium / Laboratoire d'essais</b>	IZES gGmbH, TZSB
<b>Website</b>	<a href="http://www.izes.de/tzsb/">www.izes.de/tzsb/</a>
<b>Test report id. number / Prüberichtsnummer / F</b>	SYS10_03
<b>Date of test report / G / F</b>	06.09.2011
<b>Test method / G / F</b>	ISO 9459-5 (DST)

<b>Comments of test lab / Kommentare des laboratoriums / Commentaires du laboratoire</b> *: Werte beziehen sich auf eine tägliche Entnahmerate von 600 l/Tag; values for daily draw-off rate of 600 litres/day	Stamp & signature of test lab
---	-------------------------------